

NSRP -SPC-SP 8

NSRP 0186

UMTRI

71199

FINAL REPORT  
for

TEMPORARY STAGING  
for  
SHIPYARDS

**Transportation  
Research Institute**

Prepared for

SNAME Panel SP-8  
MarAd Task ES-8-15  
Under the direction of  
H,B, Maynard & Co,

Prepared by

Industrial Engineering Department  
Bethlehem Steel Corporation  
Marine Construction Group  
Sparrows Point, Maryland  
July, 1983

Report Documentation Page				Form Approved OMB No. 0704-0188	
Public reporting burden for the collection of information is estimated to average 1 hour per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden, to Washington Headquarters Services, Directorate for Information Operations and Reports, 1215 Jefferson Davis Highway, Suite 1204, Arlington VA 22202-4302. Respondents should be aware that notwithstanding any other provision of law, no person shall be subject to a penalty for failing to comply with a collection of information if it does not display a currently valid OMB control number.					
1. REPORT DATE <b>JUL 1983</b>		2. REPORT TYPE <b>N/A</b>		3. DATES COVERED <b>-</b>	
4. TITLE AND SUBTITLE <b>Temporary Staging for Shipyards</b>				5a. CONTRACT NUMBER	
				5b. GRANT NUMBER	
				5c. PROGRAM ELEMENT NUMBER	
6. AUTHOR(S)				5d. PROJECT NUMBER	
				5e. TASK NUMBER	
				5f. WORK UNIT NUMBER	
7. PERFORMING ORGANIZATION NAME(S) AND ADDRESS(ES) <b>Naval Surface Warfare Center CD Code 2230 - Design Integration Tools Building 192 Room 128 9500 MacArthur Bldg Bethesda, MD 20817-5700</b>				8. PERFORMING ORGANIZATION REPORT NUMBER	
9. SPONSORING/MONITORING AGENCY NAME(S) AND ADDRESS(ES)				10. SPONSOR/MONITOR'S ACRONYM(S)	
				11. SPONSOR/MONITOR'S REPORT NUMBER(S)	
12. DISTRIBUTION/AVAILABILITY STATEMENT <b>Approved for public release, distribution unlimited</b>					
13. SUPPLEMENTARY NOTES					
14. ABSTRACT					
15. SUBJECT TERMS					
16. SECURITY CLASSIFICATION OF:			17. LIMITATION OF ABSTRACT <b>SAR</b>	18. NUMBER OF PAGES <b>32</b>	19a. NAME OF RESPONSIBLE PERSON
a. REPORT <b>unclassified</b>	b. ABSTRACT <b>unclassified</b>	c. THIS PAGE <b>unclassified</b>			

UMTRI

71199

LEGAL NOTICE

This report was prepared as an account of government-sponsored work. Neither the United States, nor the Maritime Administration, nor any person acting on behalf of the Maritime Administration (A) Makes any warranty or representation, expressed or implied, with respect to the accuracy, completeness or usefulness of the information contained in this report, or that the use of any information, apparatus, method, or process disclosed in this report may not infringe privately owned rights; or (B) Assumes any liabilities with respect to the use of or for damages resulting from - the use of any information, apparatus, method, or process disclosed in this report. As used in the above, "persons acting on the behalf of the Maritime Administration" includes any employee or contractor of the Maritime Administration to the extent that such employee or contractor prepares, handles, or distributes, or provides access to any information pursuant to his employment or contract with the Maritime Administration.

**Transportation  
Research Institute**

SECTION 1  
FINAL REPORT - INTRODUCTION

1.1 INTRODUCTION

A. SCOPE

This report shows the application of the labor standards for staging developed in Phase II. The application of the standards will be on an Integrated Tug-Barge (ITB) and will be used for the purpose of production control.

B, TYPES OF STAGING

There are several types of staging that apply to the ITBs. The types of staging and the areas that they apply to are listed below

1. CENTER TANK

There are five (5) center tanks on an ITB, three are 100' X 50' and the remainins two are 85' x 50'+ The staging is erected from within the tank using a grove crane. Three carpenters are in the tank. one handles the material. the other two erect the staging,

a. Smooth Bulkhead

Two board or three board bracket staging is used on smooth bulkheads. (see fig. 1)

b. Bulkheads with Floors

The floors on these bulkheads are approximtely 20' x 50' and are connected be inclined stairways. Bracket staging is locatectl at the floor level and below the floor level. (see fig. 2 & 3) Two board bracket staging is usualls used for this type of staging

c. Tank Staging Platform (see fig. 4)

A tank staging platform is used for easy access to the area below the main deck. The platform is assembled in a platen area and then placed in the center tank of the ship. Tower cranes are used to transport the tank staging platforms from the platen area to the ship. After the main deck is erected, the tank staging platform is raised (by tower crane) and secured to the main deck. The tank stagingl platforms are approximately 35'x20' and there are two per tank. The tank staging platforms are connected by three board bracket staging.

d. Boards beneath the main deck

Boards are spread beneath the. main deck from the tank staging platform to existing bracket staging+ This allows mechanics to  
●move about freely under the main deck.

# FINAL REPORT - INTRODUCTION

## SKETCHES




FIGURE 1




FIGURE 2

## INDEX

SECTION	TITLE	PAGE #
1	INTRODUCTION	1-6
1.1	INTRODUCTION	i
	SCOPE	1
	TYPES OF STAGING	1-2
	CENTER TANK	1
	WING TANK	2
	EXTERIOR SHELL	2
	PIPE STAGING	2
	LAYOUT OF THE SHIP	2
	DIFFERENCES	2
	SKETCHES	3-6
	BRACKET STAGING	3
	BULKHEAD WITH FLOORS: AT FLOOR	3
	BULKHEAD WITH FLOORS: BELOW FLOOR	4
	TANK STAGING PLATFORM	4
	WEB STAGING	5
	PIPE STAGING	5
	PLAN/SIDE VIEW: ITB .	6
2	APPLICATION OF STANDARDS	7-14
2.1	APPLICATION	7-9
	SCOPE	7
	CATALOG OF STAGING RATES	7-9
	SET-UP	7
	TEAR DOWN	8
	MATERIAL NEEDED	9
2.2	WORKSHEETS FOR PRODUCTION CONTROL	10-14
	SCOPE	10
	UNIT PRODUCTIVE HOURS - BY AREA	11
	MANHOURS - BY AREA	12
	UNIT PRODUCTIVE HOURS - SUMMARY	13
	MANHOURS - SUMMARY	14
3	EXAMPLES OF APPLICATION	15-26
3.1	WORKSHEET: UNIT PRODUCTIVE HOURS - BY AREA	15-19
	CENTER TANK (1,2,5)	15
	CENTER TANK (3,4)	16
	WING TANK (1,2,5)	17
	WING TANK (3,4)	18
	EXTERIOR SHELL	19

## INDEX

SECTION	TITLE	PAGE #
3.2	WORKSHEET: MANHOURS - BY AREA	20-24
	CENTER TANK (1,2,5)	20
	CENTER TANK (3,4)	21
	WING TANK (1,2,5)	22
	WING TANK (3,4)	23
	EXTERIOR SHELL	24
3.3	WORKSHEET: UNIT PRODUCTIVE HOURS - SUMMARY	25
3.4	WORKSHEET: MANHOURS - SUMMARY	26
4	SUMMARY	27
4.1	SUMMARY	27

## FINAL REPORT - INTRODUCTION

### 2. WING TANK

There are five (5) wing tanks on each side of an ITB, three are 100' x 30' and the remaining two are 5' x 30'. The staging is erected using the tower cranes. There are three carpenters, one is located at the material and the other two erect the staging in the wing tank.

#### a. Smooth Bulkhead

Similar to the center tank

#### b. Bulkheads with Floors

Similar to the center tank

#### c. Bulkheads with Webs

Bracket staging, either two or three board, is installed to the webs. Staging boards are spread from the bracket staging to the inboard or outboard bulkheads (see fig. 5)

### 3. EXTERIOR SHELL

On the ITBs the only staging needed on the exterior shell is at the bow and the stern of the ship. The staging is either two or three board bracket staging. There are three carpenters who erect the staging from an aerial platform. The aerial platform is held in place by a tower crane.

### 4. PIPE STAGING (see fig, 6)

Pipe staging is used at the bilge level of the exterior side shell. The pipe staging is two levels high and consists of two 16' sections connected by a span of boards.

### C. LAYOUT OF THE SHIP (see fig. 7)

The diagram shows a side view and plan view of an ITB.

### D. DIFFERENCES

The sub-ops that were developed in phase II were based on a vessel being built on a way. The vessel we are currently constructing is being built in a building basin. The basic differences in the areas is the distance that the crane has to travel from the material to the ship. Our data has been massaged to account for these differences by creating new work areas and applying our existing sub-ops to them.



# FINAL REPORT - INTRODUCTION

## SKETCHES





FIGURE 3



# FINAL REPORT - INTRODUCTION

## SKETCHES




FIGURE 5






FIGURE 6

FINAL REPORT - INTRODUCTION

SKETCHES



SIDE VIEW



PLAN VIEW

FIGURE 7.

SECTION 2  
FINAL REPORT - APPLICATION OF STANDARDS

2,1 APPLICATION

A. SCOPE

A catalog of the engineered labor standards has been established for the production control department, This catalog includes the type of staging, the applicable rates and the amount of staging material neededt

B. CATALOG

The catalog is divided into three sections: (1) Set-up, (2) Tear downs and (3) Material needed.

SECTION 1 - SET-UP	
TYPE OF STAGING	APPLICABLE RATE
10 CENTER TANK	
at Smooth bulkhead: 2 board	2.187/100 lin. ft.
: 3 board	2.356/100 lin. ft.
b. Bulkhead with floors: at floor	1.993/100 lin. ft.
: below floor	2.395/100 lin. ft.
c. Tank staging platform	0.697/100 SR. ft
d. Connections of 2 tank staging platforms	7+157/100 lin. ft.
e. Boards beneath the main deck	7.360/100 lin. ft.
2. WING TANK	
a. Webs: 2 board	3.362/100 lin. ft.
b, Smooth bulkhead: 2 board	2.414/100 lin. ft.
c, Bulkhead with floors: at floor	3.330/100 lin. ft.
: below floor	2.396/100 lin. ft.
3. EXTERIOR SHELL	
a, Bracket staging: 2 board	2.853/100 lin. ft.
4. PIPE STAGING	
a. At side shell	6.954/100 lin. ft.

## FINAL REPORT - APPLICATION OF STANDARDS

SECTION 2 - TEAR DOWN

## TYPES OF STAGING

## APPLICABLE RATE

## 1, CENTER TANK

a. Smooth bulkhead:	2 board	1.677/100	lin. ft.
	: 3 board	1.464/100	lin. ft.
b, Bulkhead with floors:	at floor	1.236/100	lin. ft.
	: below floor	1.447/100	lin. ft.
c. Tank stasins platform		0.583/100	sq. ft.
d. Connections of 2 tank stasins platforms		2.132/100	lin. ft.
e, Boards beneath the main deck		1.530/100	lin. ft.

## 2. WING TANK

a Webs: 2 board	2.268/100	lin.	ft.
b. Smooth bulkhead: 2 board	1.326/100	lin.	ft.
c. Bulkhead with floors: at floor	2.283/100	lin.	ft.
: below floor	1.497/100	lin.	ft.

### 3. EXTERIOR SHELL

a. Bracket stagins: 3 board 1.354/100 lin. ft.

#### 4. PIPE STAGING

a. At side shell 8.140/100 lin. ft.

# FINAL REPORT - APPLICATION OF STANDARDS

## SECTION 3 - MATERIAL NEEDED\*

TYPE OF STAGING	BRACKETS	STANCHIONS	BOARDS	HANDRAIL	LADDERS
1. CENTER TANK					
a. Smooth bulkhead					
(2 board	6	6	10	12	2
3 board	6	6	15	12	2
b. Bulkhead with floors					
at floor	6	12	12	12	
below floor	8	8	14	12	2
c. Connection of two Platforms	6		32		
d. Boards beneath deck			300		
2. WING TANK					
a. Webs	6	6	34	12	1
b. Smooth Bulkhead	6	6	10.	14	1
c. Bulkhead with floors					
at floor	6	6	40	10	
below floor	6	6	20	10	
3. EXTERIOR SHELL	8	8	21	14	2
4. PIPE STAGING	END PIECES	BRACES	BOARDS	STANCHIONS	HANDRAIL
	18	24	24	6	6
5. TANK STAGING PLATFORM	I-BEAMS	ANGLES	BOARDS	NUTS	8 BOLTS
	12x8: 2	3x3: 2	64	144	
	12x6 1/2: 5	4x4: 2			

NOTE: There is one stasins clip and one nut and bolt per staging bracket.  
There is 4 ladder clips per ladder. There are 2 nuts and bolts per two level pipe staging.

\* Material needed is based on 100 linear feet of bracket stasins. The tank staging platform material is based on buildins one 35' by 70' platform.

## FINAL REPORT - APPLICATION OF STANDARDS

### 2.2 WORKSHEETS FOR PRODUCTION CONTROL

#### A. SCOPE

**Worksheets have been developed for use by the production control** department. These worksheets are used to determine the unit Productive hours, manhours and the amount of the material needed. There are four worksheets: (1) Unit Productive hours - by area (ie. center tank, etc.), (2) Manhours - by area, (3) Summary of unit productive hours, and (4) Summary of manhours.

The following section shows examples of how the worksheets can be used on an Integrated Tug-Barge.

FINAL REPORT - APPLICATION OF STANDARDS

WORKSHEETS FOR PRODUCTION CONTROL  
UNIT PRODUCTIVE HOURS - BY AREA

PRODUCTION CONTROL

AREA OF SHIP:		DATE:	
TYPE OF STAGING	AMOUNT	RATE	UNIT FROD. HOURS
A. SET-UP			
1.			
2.			
3.			
4.			
5.			
TOTAL UNIT PRODUCTIVE HOURS: SET-UP			
B. TEAR DOWN			
1.			
2.			
3.			
4.			
5.			
TOTAL UNIT PRODUCTIVE HOURS: TEAR DOUN			
C. MATERIAL NEEDED			
BRACKETS		END PIECES:	
STANCHIONS:		BRACES :	
BOARDS :		I-BEAMS - 12x8:	
HANDRAIL:		- 12x6 1/2:	
LADDERS:		ANGLES - 3x3:	
STAGING CLIPS:		- 4x4:	
LADDER CLIPS:		NUTS/BOLTS:	



FINAL REPORT - APPLICATION OF STANDARDS

WORKSHEETS FOR PRODUCTION CONTROL  
MANHOURS - BY AREA

PRODUCTION CONTROL

AREA OF SHIP:	DATE:		
TYPE OF STAGING	UNIT PROD. HOURS	# MEN*	MANHOURS
A. SET-UP			
1.			
2.			
3.			
4.			
5.			

TOTAL MANHOURS: SET-UP

**B. TEAR DOWN**

- 1.
- 2.
- 3.
- 4.
- 5.

**TOTAL MANHOURS: TEAR DOWN**

\* # MEN includes the number of carpenters and welders needed to do the Job. There is usually one welder and the number of carpenters can be found in the Back-up Data on page 327



FINAL REPORT - APPLICATION OF STANDARDS

WORKSHEETS FOR PRODUCTION CONTROL  
MANHOURS - SUMMARY

PRODUCTION CONTROL

AREA OF SHIP	TYPE OF SHIP:	MANHOURS	DATE: # AREAS*	TOTAL HOURS
--------------	---------------	----------	-------------------	-------------

A. SET-UP

- 1.
- 2.
- 3.
- 4.
- 5.

TOTAL MANHOURS: SET-UP

B. TEAR DOWN

- 1.
- 2.
- 3.
- 4.
- 5.

TOTAL MANHOURS: TEAR DOWN

\* # AREAS: There are 5 center tanks, 3 are 100'x50' and 2 are 85'x50'.  
There are 10 wins tanls, 6 are 100'x30' and 4 are 85'x30'.

SECTION 3  
FINAL REPORT - EXAMPLES OF APPLICATION

3.1 WORKSHEET: UNIT PRODUCTIVE HOURS - BY AREA

PRODUCTION CONTROL			
AREA OF SHIP: CENTER TANK (1,2,5)		DATE: JUNE, 1983	
TYPE OF STAGING	AMOUNT	RATE	UNIT PROD. HOURS
A. SET-UP			
1. SMOOTH BULKHEAD			
2 BOARD	1200 FT	2.187	26.2
3 BOARD	450 FT	2.356	10.6
2. BULKHEAD WITH FLOORS			
AT FLOOR	120 FT	1.993	2.4
BELOW FLOOR	260 FT	2.395	6.2
3. TANK STAGING PLATFORM	1400 SQ FT	0.697	9.8
4. CONNECTIONS OF 2 TANK STAGING PLATFORMS	20 FT	7.157	1.4
5. BOARDS BENEATH DECK	300 FT	7.360	22.1
TOTAL UNIT PRODUCTIVE HOURS: SET UP			78.7
B. TEAR DOWN			
1. SMOOTH BULKHEAD			
2 BOARD	1200 FT	1.267	15.2
3 BOARD	450 FT	1.464	6.6
2. BULKHEAD WITH FLOORS			
AT FLOOR	120 FT	1.236	1.5
BELOW FLOOR	260 FT	1.447	3.8
3. TANK STAGING PLATFORM	1400 SQ FT	0.583	8.2
4. CONNECTIONS OF 2 TANK STAGING PLATFORMS	20 FT	2.132	0.4
5. BOARDS BENEATH DECK	300 FT	1.530	4.6
TOTAL UNIT PRODUCTIVE HOURS: TEAR DOWN			40.3
C. MATERIAL NEEDED			
BRACKETS - 2 BOARD: 104	END PIECES: -		
- 3 BOARD: 22			
STANCHIONS: 126	BRACES: -		
BOARDS: 678	I-BEAM - 12x8: 4		
HANDRAIL: 222	- 12x6 1/2: 10		
LADDERS: 40	ANGLES - 3x3: 4		
STAGING CLIPS: 126	- 4x4: 4		
LADDER CLIPS: 160	NUTS/BOLTS: 392		

# FINAL REPORT - EXAMPLES OF APPLICATION

## WORKSHEET: UNIT PRODUCTIVE HOURS - BY AREA

PRODUCTION CONTROL		DATE: JUNE, 1983	
AREA OF SHIP: CENTER TANK (3.4)			
TYPE OF STAGING	AMOUNT	RATE	UNIT PROD. HOURS
A. SET-UP			
1 SMOOTH BULKHEAD			
2 BOARD	990 FT	2.187	21.7
3 BOARD	420 FT	2.356	9.9
2. BULKHEAD WITH FLOORS			
AT FLOOR	120 FT	1.993	2.4
BELOW FLOOR	260 FT	2.395	6.2
30 TANK STAGING PLATFORM	1400 SQ FT	0.697-	9.8
4. CONNECTIONS OF 2 TANK			
STAGING PLATFORMS	20 FT	7.157	1.4
!3. BOARDS BENEATH DECK	300 FT	7.360	22.1
TOTAL UNIT PRODUCTIVE HOURS: SET-UP			73.5
B. TEAR DOWN			
1. SMOOTH BULKHEAD			
2 BOARD	990 FT	1.267	12.5
3 BOARD	420 FT	1.1464	6.1
2. BULKHEAD WITH FLOORS			
AT FLOOR	120 FT	1.236	1.5
BELOW FLOOR	260 FT	1.447	3.8
3. TANK STAGING PLATFORM	1400 SQ FT	0.583	8.2
4. CONNECTIONS OF 2 TANK			
STAGING PLATFORMS	20 FT	2.132	0.4
5 BOARDS BENEATH DECK	300 FT	1.530	4.6
TOTAL UNIT PRODUCTIVE HOURS: TEAR DOWN			37.1
C. MATERIAL NEEDED			
BRACKETS - 2 BOARD: 80		END PIECES:	
- 3 BOARD: 18			
STANCHIONS: 102		I-BEAMS - 12x8: 4	
BOARDS: 612		-12x6 1/2: 10	
LADDERS: 40		ANGLES - 3x3: 4	
STAGING CLIPS: 98		- 4x4: 4	
LADDER CLIPS: 160		NUTS/BOLTS: 368	

# FINAL REPORT - EXAMPLES OF APPLICATION

## WORKSHEET: UNIT PRODUCTIVE HOURS - BY AREA

PRODUCTION CONTROL		DATE: JUNE. 1983	
AREA OF SHIP: WING TANK (1,2,5)			
TYPE OF STAGING	AMOUNT	RATE	UNIT PROD. HOURS
A. SET-UP			
1. WEBS	1120 FT	3.362	37.7
2. SMOOTH BULKHEAD	300 FT	2.414	7.2
3. BULKHEAD WITH FLOORS			
AT FLOOR	250 FT	3.350	8.4
BELOW FLOOR	250 FT	2.396	6.0
TOTAL UNIT PRODUCTIVE HOURS: SET-UP			59.3
B. TEAR DOWN			
1. WEBS	1120 FT	2.268	25.4
2. SMOOTH BULKHEAD	300 FT	1.326	4.0
3. BULKHEAD WITH FLOORS			
AT FLOOR	250 FT	2.283	5.7
BELOW FLOOR	250 FT	1.497	3.7
TOTAL UNIT PRODUCTIVE HOURS: TEAR DOWN			38.8
C. MATERIAL NEEDED			
BRACKETS - 2 BOARD: 106.		END PIECES: -	
STANCHIONS: 106		BRACES: -	
BOARDS: 560		I-BEAMS - 12x8: -	
HANDRAIL: 226		- 12X6 1/2:	
LADDERS: 21		ANGLES - 3x3: -	
STAGING CLIPS: 92		- 4x4: -	
LADDER CLIPS: 84		NUTS/BOLTS: 106	

# FINAL REPORT - EXAMPLES OF APPLICATION

## WORKSHEET: UNIT PRODUCTIVE HOURS - BY AREA

AREA OF SHIP: WING TANK (3,4)		PRODUCTION CONTROL	DATE: JUNE, 1983	
TYPE OF STAGING	AUOUNT	RATE	UNIT PROD. HOURS	
A. SET-UP				
1. WEBS	900 FT	3.362	30.3	
2. SMOOTH RULKHEAD	300 FT	2.414	7.2	
3. BULKHEAD WITH FLOORS				
AT FLOOR	250 FT	3.350	B . 4	
BELOW FLOOR	250 FT	2.396	6.0	
TOTAL UNIT PRODUCTIVE HOURS: SET-UP			51.9	
B. TEAR DOWN				
1. WEBS	900 FT	2.268	20.4	
2. SMOOTH BULKHEAD	300 FT	1.326	4.0	
3. BULKHEAD WITH FLOORS				
AT FLOOR	250 FT	2.283	5.7	
BELOW FLOOR	250 FT	1.497	3.7	
TOTAL UNIT PRODUCTIVE HOURS: TEAR DOWN			33.8	
C. MATERIAL NEEDED				
BRACKETS - 2 BOARD: 92			END PIECES: -	
STANCHIONS: 92			BRACES: -	
BOARDS: 486			I-BEAMS - 12x8:	
HANDRAIL: 200			- 12X6 1/2: -	
LADDERS: 21			ANGLES - 3x3: -	
STAGING CLIPS: 92			0- 4x4: -	
LADDER CLIPS: 84			NUTS/BOLTS: 92	

# FINAL REPORT - EXAMPLES OF APPLICATION

## WORKSHEET: UNIT PRODUCTIVE HOURS - BY AREA

PRODUCTION CONTROL			
AREA OF SHIP: EXTERIOR SHELL		DATE: JUNE. 1983	
TYPE OF STAGING	AMOUNT	RATE	UNIT PROD. HOURS
A. SET-UP			
1. BRACKET STAGING			
BOW	960 FT	2.855	27.4
STERN	3700 FT	2.855	105.6
20 PIPE STAGING	1100 FT	6.954	76+S
TOTAL UNIT PRODUCTIVE HOURS: SET-UP			209.5
B. TEAR DOWN			
1. BRACKET STAGING			
Bow	960 FT	1.354	13.0
STERN.	3700 FT	1.354	50.1
2. PIPE STAGING	1100 FT	8 . 1 4 0	8 9 . 5
TOTAL UNIT PRODUCTIVE HOURS: TEAR DOWN			152.6
C. MATERIAL NEEDED			
BRACKET STAGING - 3 BOARD: 374		END PIECES: 19S	
STANCHIONS: 440		BRACES: 264	
BOARDS: 1244		I-BEAMS - 12x8:	
HANDRAIL: 716		- 12X6 1/2:	
LADDERS: 94		ANGLES - 3x3:	
STAGING CLIPS: 374		- 4x4: -	
LADDER CLIPS: 376		NUTS/BOLTS: 814	



# FINAL REPORT - EXAMPLES OF APPLICATION

## 3.2 WORKSHEET: MANHOURS - BY AREA

PRODUCTION CONTROL				
AREA OF SHIP: CENTER TANK (1,2,5)		DATE: JUNE, 1983		
TYPE OF STAGING	UNIT	PROD. HOURS	# MEN*	MANHOURS
A. SET-UP				
1. SMOOTH BULKHEAD				
2 BOARD		26.2	4	104.8
3 BOARD		10.6	4	42.4
2. BULKHEAD WITH FLOOR				
AT FLOOR		2.4	4	9.6
BELOW FLOOR		6.2	4	24.8
3. TANK STAGING PLATFORM		9.8	2	19.6
40 CONNECTIONS OF 2 TANK				
STAGING PLATFORMS		1.4	3	4.2
5. BOARDS BENEATH DECK		22.1	2	44.2
TOTAL MANHOURS: SET-UP				249.6
B. TEAR DOWN				
1. SMOOTH BULKHEAD				
2 BOARD		15.2	6	91.2
3 BOARD		6.6	6	39.6
2. BULKHEAD WITH FLOORS				
AT FLOOR		1.5	6	9.0
BELOW FLOOR		3.8	6	22.8
3. TANK STAGING PLATFORM		8.2	6	49.2
4. CONNECTIONS OF 2 TANK				
STAGING PLATFORMS		0.4	6	2.4
5. BOARDS BENEATH DECK		4.6	6	27.6
TOTAL HANHOURS: TEAR DOWN				241.8

X # MEN includes the number of carpenters and welders needed to do the job. There is usually one welder (except for tank staging platforms and boards beneath the deck) and the number of carpenters can be found in the Rack-up Data on page 327.

# FINAL REPORT - EXAMPLES OF APPLICATION

## WORKSHEET: MANHOURS - BY AREA

PRODUCTION CONTROL  
AREA OF SHIP: CENTER TANK (3,4)

DATE: JUNE, 1983

TYPE OF STAGING	UNIT PROD, HOURS	# MEN*	MANHOURS
A. SET-UP			
1. SMOOTH BULKHEAD			
2 BOARD	21.7	4	86.8
3 BOARD	9.9	4	39.6
2. BULKHEAD WITH FLOORS			
AT FLOOR	2.4	4	9.6
BELOW FLOOR	6.2	4	24.8
3. TANK STAGING PLATFORM	9.8	2	19.6
4. CONNECTIONS OF 2 TANK STAGING STAGING PLATFORMS	1.4	3	4.2
5. BOARDS BENEATH DECK	22.1	2	44.2
TOTAL MANHOURS: SET-UP			228.8
B. TEAR DOWN			
1. SMOOTH BULKHEAD			
2 BOARD	12.5	6	75.0
3 BOARD	6.1	6	36.6
2. BULKHEAD WITH FLOORS			
AT FLOOR	1.5	6	9.0
BELOW FLOOR	3.8	6	22.8
3. TANK STAGING PLATFORM	8.2	15	49.2
4. CONNECTIONS OF 2 TANK STAGING PLATFORMS	0 . 4	6	2.4
5. BOARDS BENEATH DECK	4.6	6	27.6
TOTAL MANHOURS: TEAR DOWN			222.6

\* # MEN includes the number Of carpenters and welders needed to do the job. There is usually one welder (except for tank stasins platforms and boards beneath the deck) and the number of carpenters can be found in the Back-up Data on Page 327.

# FINAL REPORT - EXAMPLES OF APPLICATION

## WORKSHEET: MANHOURS - BY AREA

PRODUCTION CONTROL		DATE: JUNE, 1983	
AREA OF SHIP: WING TANK (1,2,5)			
TYPE OF STAGING	UNIT PROD. HOURS	# MEN*	MANHOURS
A. SET-UP			
10 WEBS	37.7	4	150.8
2. SMOOTH BULKHEAD	7.2	4	28.13
3. BULKHEAD WITH FLOORS			
AT FLOOR	8.4	4	33.6
BELOW FLOOR	6.0	4	24.0
TOTAL MANHOURS: SET-UP			237.2
B. TEAR DOWN			
1.WEBS	25.4	6	152.4
2. SMOOTH BULKHEAD	4.0	6	24.0
3. BULKHEAD WITH FLOORS			
AT FLOOR	5.7	6	34.2
BELOW FLOOR	3.7	6	22.2
TOTAL MANHOURS: TEAR DOWN			232.8

\* # MEN includes the number of carpenters and welders needed to to the job. There is usually one welder and the number of carpenters can be found in the Back-up Date on page 327.

# FINAL REPORT - EXAMPLES OF APPLICATION

## WORKSHEET: MANHOURS - BY AREA

PRODUCTION CONTROL		DATE: JUNE, 1983		
AREA OF SHIP: WING TANK (3,4)				
TYPE OF STAGING	UNIT PROD. HOURS	# MEN*	MANHOURS	
A. SET-UP				
1. WEBS	30.2	4	121.2	
2. SMOOTH BULKHEAD	7.2	4	28.8	
3. BULKHEAD WITH FLOORS				
AT FLOOR	8.4	4	33.6	
BELOW FLOOR	6.0	4	24.0	
TOTAL MANHOURS: SET-UP			207.6	
B. TEAR DOWN				
1. WEBS	20.4	6	122.4	
2. SMOOTH BULKHEAD	4.0	6	24.0	
3. BULKHEAD WITH FLOORS				
AT FLOOR	5.7	6	34.2	
BELOW FLOOR	3.7	6	22.2	
TOTAL MANHOURS: TEAR DOWN			202.8	

# MEN includes the number of carpenters and welders needed to do the job. There is usually one welder and the number of carpenters can be found in the Back-IP Data on Page 327.

# FINAL REPORT - EXAMPLES OF APPLICATION

## WORKSHEET: MANHOURS - BY AREA

PRODUCTION CONTROL			
AREA OF SHIP: EXTERIOR SHELL	DATE: JUNE, 1983		
TYPE OF STAGING	UNIT PROD. HOURS	# MEN*	HANHOURS
A. SET-UP			
1. BRACKET STAGING			
BOW	27.4	4	109.6
STERN	105.6	4	422.4
2. PIPE STAGING	76.5	4	306.0
TOTAL MANHOURS: SET-UP			838.0
B. TEAR DOWN			
1. BRACKET STAGING			
BOW	13.0	3	39.0
STERN	50.1	3	150.3
20 PIPE STAGING	89.5	3	268.5
TOTAL MANHOURS: TEAR DOWN			457.8

# MEN includes the number of carpenters and the welders needed to do the job. There is usually one welder and the number of carpenters can be found in the Back-up Data on page 327.

# FINAL REPORT - EXAMPLES OF APPLICATION

## 3.3 WORKSHEET: UNIT PRODUCTIVE HOURS - SUMMARY

PRODUCTION CONTROL			
TYPE OF SHIP: INTEGRATED-TUG-BARGE		DATE: JUNE, 1983	
AREA OF SHIP	UNIT PROD. HOURS	# AREAS*	TOTAL HOURS
A. SET-UP			
1. CENTER TANK (1,2,5)	79.7	3	236.1
2. CENTER TANK (3,4)	73.5	2	147.0
3. WING TANK (1,2,5)	59.3	6	355.8
4. WING TANK (3,4)	38.8	4	155.2
5. EXTERIOR SHELL	209.5	1	209.5
TOTAL UNIT PRODUCTIVE HOURS: SET-UP			1103.6
R. TEAR DOWN			
1. CENTER TANK (1,2,5)	40.3	3-	120.9
2. CENTER TANK (3,4)	37.1	2	74.2
3. WING TANK (1,2,5)	51.9	6	311.4
4. WING TANK (3,4)	33.8	4	135.6
5. EXTERIOR SHELL	152.6	1	152.6
TOTAL UNIT PRODUCTIVE HOURS: TEAR DOWN			794.3
C. TOTAL MATERIAL NEEDED			
BRACKETS - 2 BOARD: 974		END PIECES: 198	
- 3 BOARD: 476			
STANCHIONS: 1524		BRACES: 264	
ROADS: 7154		I-BEAMS - 12x8: 20	
HANDRAIL: 2848		- 12X6 1/2: 50	
LADDERS: 399		ANGLES - 3x3: 20	
STAGING CLIPS: 1450		- 4x4: 20	
LADDER CLIPS: 1595		NUTS/BOLTS: 3S96	

\* # AREAS: There are 5 center tanks, 3 are 100'x50' and 2 are 85'x50'.  
 There are 10 wing tanks, 6 are 100'x30' and 4 are 85'x30'.  
 Exterior shell consists of bracket stasins on the shell (at bow and stern) and Pipe staging at the side shell.

# FINAL REPORT - EXAMPLES OF APPLICATION

## 3.4 WORKSHEET: MANHOURS - SUMMARY

PRODUCTION CONTROL			
TYPE OF WORK: INTEGRATED TUG-BARGE		DATE: JUNE, 1983	
AREA OF SHIP	MANHOURS	# AREAS*	TOTAL HOURS
A. SET-UP			
1. CENTER TANK, (1,2,5)	249.7	3	749.1
2. CENTER TANK, (3,4)	228.8	2	457.6
3. WING TANK (1,2,5)	237.2	6	1423.2
4. WING TANK (3,4)	207.6	4	830.4
5. EXTERIOR SHELL	838.0	1	838.0
TOTAL MANHOURS: SET-UP			4298.5
B. TEAR DOWN			
1. CENTER TANK (1,2,5)	241.8	3	725.4
2. CENTER TANK (3,4)	228.6	2	457.2
3. WING TANK (1,2,5)	232.8	6	1396.8
4. WING TANK (3,4)	202.8	4	811.2
5. EXTERIOR SHELL	457.8	1	457.8
TOTAL MANHOURS: TEAR DOWN			3948.4

\* # AREAS: There are 5 center tanks, 3 are 100'X50' and 2 are 85'x50'.  
 There are 10 wing tanks, 6 are 100'x30' and 4 are 85'X50'.  
 Exterior shell consists of bracket stasins on the shell (at bow and stern) and pipe staging at the side shell

SECTION 4  
FINAL REPORT - SUMMARY

4.1 SUMMARY

The worksheets that were developed for this final report and the information that they contain will be very useful to several departments in the shipyard. For example: (1) Production control: for scheduling and manpower leveling; (2) Carpenter department: for manpower scheduling and **material ordering; (3) Industrial Engineering: for incentive development** and progress; and (4) Estimating: for use in estimating new work.

All of the necessary back-up data is included with this report. The back-up data consists of the following: (1) Work areas, (2) Manual - methods, (3) Timesheets, (4) Time standards, and (5) Method analysis.



**Transportation  
Research Institute**